

P

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
MAR 22 1967  
03-22-1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

15-065-03186-00-00

Operator's Full Name Ivy Oil Company,

Complete Address: Box # 86, Plainville, Kansas.

Lease Name Griffith Well No. 1

Location SW-SW-NE Sec. 25 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 4052

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight casing Pulling Company,

Address: Box # 405, Chase, Kansas. License No. 346

Operation Completed: Hour 1:30 PM Day 18 Month 3 Year 1967

The Above well was plugged as follows:

194' -- 8 5/8" Surface pipe, cement circulated with 200 Sx.  
3830' -- 5 1/2" Production casing cemented with 100 Sx. Top of cement @  
3200' (Temp. Survey). Top perforations from 3611' to 3616'.

Sanded well back to 3600' and set 5 Sx. cement with dump bailer. Pulled  
5 1/2" to 700' and circulated heavy gel mud. (Used 25 Sx. Gel). Pulled 5 1/2"  
to 600' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 180' and  
displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set rock bridge @ 30'  
and 10 Sx. cement to bottom of cellar. (Recovered 2978' 5 1/2" casing).

(Mudding and Cementing operations performed by Sun Oil Well Cementing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. R. Nichols  
Well Plugging Supervisor

DATE 3/22/67

FILE NO. 4939-W.