

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1968

CONSERVATION DIVISION
Wichita, Kansas

10-28-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-00443-00-00

Operator's Full Name Ivy Oil Company,

Complete Address: Box #86, Plainville, Kansas.

Lease Name McCall Well No. B-1

Location NE-NE-SW Sec. 25 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 4145

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company, Incorporated,

Address: Box #405, Chase, Kansas . License No. 436

Operation Completed: Hour 10:30 AM Day 26 Month 10 Year 1968

The Above well was plugged as follows:

208'--8 5/8" Surface casing, cement circulated with 150 Sx.

3845'--5 1/2" casing cemented on bottom with 75 Sx. Top perforations @ 3596' with well plugged back to 3830'.

Pushed plug to 3575' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well with initially 16 sacks gel with 5 sacks hulls in initial gel and followed with 100 Sx. cement from 950' to 625' then 11 sacks gel from 625' to 200' and followed with 20 Sx. cement from 200' to 140' then 3 sacks gel from 140' to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure--600#. Final shut-in pressure--300#.

I hereby certify that the above well was plugged as herein stated.

INDEXED

Signed: W. S. Dickels
Well Plugging Supervisor

DATE 10/28/68
INV. NO. 8711-44