

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

SEP 13 1977
09-13-1977

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 193 - 20,143-00-00 (of this well)

Operator's Full Name Chief Drlg Co., Inc. & Bill J. Porter

Complete Address 905 Century Plaza, Wichita, Kansas

Lease Name Dell Well No. 1

Location C S/2 S/2 SW/4 Sec. 6 Twp. 10 Rge. (E) (W) 33

County Thomas Total Depth 4801

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 8:45 P Day 11 Month 9 Year 1977

The above well was plugged as follows:

RTD 4801' 8 5/8 csg set 382' cwc 225 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 1650' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Manney
Well Plugging Supervisor

DATE 9-13-77

INV. NO. 5835-W