

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 15 1974  
11-15-1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-193-20053-00-00

Operator's Full Name F & M Oil Company, Incorporated,

Complete Address 603 Union Center, Wichita, Kansas.

Lease Name Kriss Well No. 1

Location CNW-NE Sec. 3 Twp. 10 Rge. (E) (W) 34

County Thomas Total Depth 4830'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Abercrombie Drilling, Incorporated,

Address 801 Union Center, Wichita, Kansas, License No. \_\_\_\_\_

Operation Completed: Hour 7:00 AM Day 7 Month 11 Year 1974

The above well was plugged as follows:

312'--8 5/8" Surface casing, cement circulated with 210 Sx.  
Top of Dakota section @ 1525'.

Circulated hole with heavy mud. Pulled DP to 1750' and displaced 110 Cu. Ft. cement  
thru DP from 1750' to 1425'. Pulled DP to 315' and displaced 30 Cu. Ft. cement thru  
DP from 315' to 240'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 11/15/74  
INV. NO. 307-w