

6 031548

6-13

189

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-20,949 - 0020

W/2 W/2 NW, SEC. 24, T 9 S, R 23 W/E

3960 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6861

Lease Name Ninemire Well # 1

Operator: Ron's Oil Operations, Inc.

County Graham 128.86

Name & Address R.R. 1 Box 194

Well Total Depth 3965 feet

Penokee, Kansas 67659

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 167'

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing License Number 6050

Address Chase, Kansas

Company to plug at: Hour: A.M. Day: 13 Month: 6 Year: 19 91

Plugging proposal received from Bill

(company name) Kelso Casing (phone)

were: 8 5/8 set @ 167' w/175 sx. 4 1/2 set @ 3925' w/175 sx. Perf. 3848'-52

Order 225 sx. 65/35 poz. 10% Gel. 500# Hulls. Allied Cement Company.

Order sand & common cement. Pull pipe.

RECEIVED
STATE CORPORATION COMMISSION
7-1-91

Allied wire line past anhy. to 2000'.

III 01 1991

Plugging Proposal Received by Carl Goodrow CONSERVATION DIVISION
(TECHNICIAN) Wichita, Kansas

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:30 A.M. Day: 13 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT Sand back to 3790' w/4 sx. com. cement on sand w/bailer.

First shot @ 1900' top anhy. Couldn't pull. Recovered 1307' from free point shot.

Squeezed 8 5/8 w/225 sx. cement blend w/500# hulls. Max. P.S.I. 1500#

Close in 1000#. Plug complete. No salt section in area of any significance. Hole

took cement with no pressure until last few sacks. Then it locked up.

Remarks: Cement from 2000' to surface with plastic wrap pipe across C.H. - cemented in.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JUL 19 1991

INV. NO. 32311

G.S.

Signed Carl Goodrow
(TECHNICIAN)