

To: 6 041089
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-7 065-30008-0000
API NUMBER 15- 11-1964

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Operator: Petroleum Inc.
Name &
Address 301 N. Main
Suite 900
Wichita, Ks. 67202

App C , SEC. 25, T 9 S, R 23 W/EX
NW NE 4620 feet from S section line
1880 feet from E section line

Lease Name Redline UniWell # 3-2

County Graham 128.05

Well Total Depth 3940 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 221' w/175
sks

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number

Address Hays, Ks.

Company to plug at: Hour: 9:00AM Day: 7 Month: November Year: 19 89

Plugging proposal received from Everett Jones

(company name) Pet Inc. (phone)

were: 5 1/2" casing set at 3937' w/125 sks: Perf at 3849' - 3971'. Perf anhy at 1990'

and base dakota at 1140': Ordered 350 sks 65/35 poz 10% gel w/1/2" f.c. plus 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:00 PM Day: 7 Month: Nov Year: 19 89

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing: 300 sks cemnt w/ 4 sks hulls.

Max psi 900# S.T. 500#.

Pumped in 8 5/8" s.p.: 50 sks cement w/1 sk hulls.

Max psi 300# S.T. 100#.

RECEIVED
STATE CORPORATION COMMISSION
1-3-90
JAN 3 1990

Remarks:
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 04 1990

INV. NO. 26869

Handwritten initials

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel