

6 031148

8-9 065-30190-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1966

C E1 SB SEC. 26, T 9 S, R 23 W/E

1320 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5285

Lease Name Hill City, Ks Well # 8

Operator: The Dane G. Hansen Trust

County High School Graham 127.89

Name & Address Box 187

Well Total Depth 3935 feet

Logan, Ks. 67646

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 196

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number

Address Russell, Ks.

Company to plug at: Hour: AM Day: 9 Month: August Year: 19 88

Plugging proposal received from Johnnie Parsons

(company name) D G Hansen (phone)

were: 8 5/8" set at 196' w/140 sks cwc. 4 1/2" set at 3924' w/175 sks.

Squeezed at 3427' w/50 sks. 3180' w/300 sks 2700' w/200 sks. Perf at 1160' Dk block

squeeze. Order 300 sks Cement Blend and 600# Hulls. Allied Cement Co. Water Truck

w/QWS Truck.

RECEIVED
STATE CORPORATION COMMISSION
9-16-88
SEP 16 1988

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed Hour: 10:40AM Day: 9 Month: August Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 4 1/2" w/200 sks Cement Blend w/5 sks Hulls mixed

into max Psi of 300# closed in at 300# Psi. Squeezed 8 5/8" w/100 sks Cement Blend

w/1 sks Hulls to max Psi 500#. Close in Psi 500#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
to be preserved this plugging.

DATE 9-21-88

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 22344

Carl Goodrow