

8-1-88

6 031174

API NUMBER 15-065-01567-0001 ¹⁹⁵⁷

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NE NW, SEC. 28, T 9 S, R 23 W&E
4950 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7448

Lease Name Morris Well # 5

Operator: Burch Exp Inc.

County Graham 128.15

Name & Address 11225 Edinborough Way

Well Total Depth 3943 feet

Parker, Colorado 80134

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well ~~/~~ Gas Well Input Well ^{RT} X KCSWD Well U&A

Other well as hereinafter indicated C 7,991

Plugging Contractor Poe Well Service License Number

Address Oberlin, Ks.

Company to plug at: Hour: PM Day: 1 Month: Aug Year: 19 88

Plugging proposal received from Mel Taylor

(company name) Burch (phone)

were: 8 5/8" set at 208' w/175 sks 5 1/2" 3942' w/150 sks. Perf 3921' - 25'.

Order 200 sks 60/40 Poz 8% Gel 500# Hulls. Halliburton Cement Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: Day: 1 Month: August Year: 19 88

ACTUAL PLUGGING REPORT Ran tubing and bit, washed down Cedar Hill sand to anhydrite.

Circulated cement to surface w/175 sks. Tied onto casing. Squeezed 200# Closed in.

Squeezed backside w/25 sks cement to 300#. Close in. Plug completed.

RECEIVED

STATE CORPORATION COMMISSION

3-14-89
MAR 14 1989

CONSERVATION DIVISION
Wichita, Kansas

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 3-16-89

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 24118