

6 030873

5-87  
API NUMBER 15-065-01558-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW SE NW, SEC. 28, T 9 S, R 23 W E  
3630 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7448

Lease Name Morris Well # 2

Operator: Burch Drilling Co., Inc.

County Graham 130.98

Name & Address 11190 Cambridge Court

Well Total Depth 4030 feet

Parker, Colorado 80134

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor B.J. Titan License Number \_\_\_\_\_

Address Hays, Kansas

Company to plug at: Hour: AM Day: 1 Month: 5 Year: 19 87

Plugging proposal received from Mel Taylor

(company name) Burch Drilling (phone) \_\_\_\_\_

were: Order 200 sk 65/35 poz 10% gel 2% Dical 5 sx hulls. B.J. Titan Cmt. Co.

Rush Water Trucks, Wash over pipe and sand to 2100' (anhy) circulate cmt to surface with pipe mix and pump on backside well squeezed twice.

Plugging Proposal Received by Carl Goodrow Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9 AM Day: 1 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 8 5/8" set at 208' with 175 sks 5 1/2" set at 4029' with 125 sks

Bottom sanded off mix and pumped down 5 1/2 55 bbl. (110 sx) Max 600# PSI Close in 600 #

mix and pump down annulus 50 bbl. (100 sx) max. PSI 300 # close in 150 # with 5sx hulls

STATE OF KANSAS JUN 25 1987

6-25-87  
JUN 25 1987

Remarks: \_\_\_\_\_

(If additional description is necessary, use BACK of this form.) Kansas

INVOICED  
In addition to (if applicable) observe this plugging.

DATE 6-25-87

INV. NO. 17348

Signed Carl Goodrow  
(TECHNICIAN)

Carl Goodrow

DB