

22

4-032177

Received

9-25

KCC

02109 - 0001

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-065-

C S2 SW NE /4 SEC. 31, 09, 23 W  
2790 feet from S section line  
1980 feet from E section line

Operator license# -

Lease: White Well # 1

Operator: State of Kansas Fee Fund

County: Graham

Address: 2301 E. 13th Street - Dist. #4  
Hays, Kansas 67601  
Control No: 970122

Well total depth 4206 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 209 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 25 Month: September Year: 1996

Plugging proposal received from: Carl Goodrow - District #4 Staff

Company: State of Kansas Phone: 913-628-1200

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Order sand and common cement.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ X ], Part[ ], None[ ]

Completed: Hour: 9:00 A.M., Day: 25, Month: September, Year: 1996

Actual plugging report: 8 5/8" set at 209' w/140 sxs cwc. 4 1/2" set at 4206' with N/A sxs. Prod. perf. 3795' - 4018'. Sanded back to 3700' w/4 sxs common cement on sand with bailer. No stretch on 4 1/2" casing "at all". Shot at 2050' and 1200'. Mixed and pumped down 4 1/2" with 230 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 1000#. Held. Load 8 5/8" annulus with 1 1/4 bbl. slurry 5 sxs cement. Used total of 235 sxs cement blend with 500# hulls. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plugin: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING. Elevation: GL

I did[ X ] / did not[ ] observe the plugging.

Carl Goodrow  
(agent)

Form CP-2/3