

15-005-30159-0000

12,785

190R

6 041250

API NUMBER 15- 8-14-66

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE SW, SEC. 31, T 9 S, R 23 W Ex

435 feet from S section line

3095 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Hoof NW Well # 113 S

Operator: Oxy U.S.A. Inc.

County Graham 67.43

Name & Address Box 26100

Well Total Depth 2075 feet

Oklahoma City, OK. 73126-0100

Conductor Pipe: Size feet

Surface Casing: Size feet

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated Supply Well

Plugging Contractor Halliburton Cementing License Number

Address Great Bend, Ks.

Company to plug at: Hour: 9:00AM Day: 15 Month: Jan Year: 19 91

Plugging proposal received from J. D. Hinniger

(company name) OXY USA (phone)

were: 7" casing set at 2061 w/600sks cement; perfs at 1760 to 1800.

Base dakota at 1397. Ordered 300 sks 65/35 poz 10% gel w/1/4 lb f.c. plus 3 sks hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:00PM Day: 15 Month: Jan Year: 19 91

ACTUAL PLUGGING REPORT R. I. H. w/tubingw/tubing to 1450; circ cement to surf w/150 sks. cement. P.O.O.H. w/tubing: Hook up to 7" casing, sq 25 sks cement in casing. Max 400 lbs. psi. S.I. 300 lbs. psi.

1-28-91
16281991

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

(did / did not) observe this plugging.

DATE FEB 13 1991

WEL. NO. 30717

JLS

Signed Dennis L. Hamel (TECHNICIAN)

Dennis Hamel