

4-7 065-20366-0000

6 031231

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1970  
C SW SE, SEC. 32, T 9 S, R 23 W/E  
660 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5145  
Operator: Dreiling Oil Inc.  
Name & Address: Box 1000  
Victoria, Ks. 67671

Lease Name Woodward Well # 1  
County Graham 130.81  
Well Total Depth 4025 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 174

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cement Co. License Number \_\_\_\_\_

Address Russell, Ks.

Company to plug at: Hour: \_\_\_\_\_ PM Day: 4 Month: April Year: 19 89

Plugging proposal received from Ivan

(company name) Dreiling Oil (phone) \_\_\_\_\_

were: 8 5/8" set at 174' w/140 sks. 4 1/2" set at 4024 w/150 sks. Perf 3837 -3942.

Perf at 1300 for squeeze. Squeezed at 1595 w/60 sks 1675' w/200 sks - 2855 - 80 w/175 sks.

3100' - 3240' w/200 sks. Order 300 sks 65/35 Pozmix 10% Gel 2% Dical 500# Hulls. Allied Cement

Co. Keller Water Trucks and company trucks.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:00PM Day: 4 Month: April Year: 19 89

ACTUAL PLUGGING REPORT Squeezed 4 1/2" w/200 sks cement blend w/500# Hulls mixed into

max psi 900# Close in psi 500#. Squeezed 8 5/8" w/100 sks to max psi 400#. Close in 200#. Plug

complete.

RECEIVED  
STATE CORPORATION COMMISSION  
4-19-89  
APR 19 1989

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-24-89

INV. NO. 24466

Signed Carl Goodrow  
(TECHNICIAN)  
Carl Goodrow