

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22140-00-00
Spot: SENEŠWNW Sec/Twnshp/Rge: 32-9S-23W
3418 feet from S Section Line, 4078 feet from E Section Line
Lease/Unit Name: MYERS-JUSTICE Well Number: 2
County: GRAHAM Total Vertical Depth: 3990 feet

Operator License No.: 30076
Op Name: A & A PRODUCTION
Address: PO BOX 100
HILL CITY, KS 67642

Conductor Pipe: Size feet: 8 1/29.68
Surface Casing: Size 8.625 feet: 255 170 SX CMT
Production: Size 4.5 feet: 3968 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/08/2002 9:00 AM
Plug Co. License No.: 30076 Plug Co. Name: A & A PRODUCTION
Proposal Rcvd. from: ANDY ANDERSON Company: A & A PRODUCTION Phone: (785) 421-6266

Proposed Plugging Method: Order 420 cu.ft. cement slurry.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/08/2002 11:00 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 255' w/170 sxs cwc. 4 1/2" set at 3968' w/125 sxs.
D.V. set at 2034' w/450 sxs cwc.
Prod. Perfs 3968' - 3990'.
Fluid level near bottom of depleted zone.
Filled 4 1/2" casing with 420 cu.ft. cement slurry to surface.
Plug complete.

RECEIVED
3-12-02
MAR 12 2002
KCC WICHITA

Remarks:

Plugged through: CSG

INVOICED
DATE March 13-02
NO. 2002061520

District: 04

101

Signed Carl Goodrow
(TECHNICIAN)

INVOICED

Form CP-2/3


MAR 07 2002

DATE

ROBERT W. MYERS
 11945 FORESTWOOD DR. #2 MYERS-JUSTICE 32-9-23W
 DALLAS, TX 75234 1862' FNL&
 CONTR EMPHASIS OIL OPERATIONS CTY GRAHAM 1202' FWL, NW/4

GEOL BEN LANDIS FIELD BUTCHER

ELV 2361 KB SPD 2/15/85 CARD ISSUED 5/23/85 IP P 10 BO & 22 BWPD
 2356 GL DRLG COMP 2/24/85 LKC OH 3968-3990



SMP	Tops	Depth/Datum	API 15-065-22,140
			8 5/8 " 255 / 170SX, 4 1/2 " 3968 / 125SX, MULTI STAGE COLLAR 2034 / 450SX
ANH	2138 + 223		NO CORES
HEEB	3787-1426		DST (1) 3889-3914 (LKC) / 30-60-30-60, (1ST OP) FB / 4", (2ND OP) NB, REC 120' WM, SIP 497-487#, FP 62-93 / 62-93#, HP 1952-1901#
TOR	3814-1453		
LANS	3829-1468		DST (2) 3944-90 (LKC) / 30-60-60-90, (1ST OP) SB OFF BTM OF BKT / 11", (2ND OP) SB OFF BTM OF BKT / 14", 70' GIP, REC 60' HVY OIL SPTD M, 60' WMCO (10% W, 20% M, 50% OIL), 60' WMCO (45% OIL, 20% G, 5% W, 30% M), 60' WMCO (65% OIL, 20% G, 5% W, 10% M), SIP 620-490#, FP 72-82 / 82-114#, HP 2014-1983#
BKC	NOT REACHED		
RTD	3990-1629		MICT - CO, (LKC OH), SWB DWN, GSO, NAT, SET 2 3/8 " TBG AT 3968', POP, P 10 BO & 22 BWPD (GR 38°), 3/24/85

NOTE: CORRECTION: 3/7/85 - ORIGINALLY FIRST REPORTED IN 32-9-22W

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS