


STATE CORPORATION COMMISSION

15-065-00010-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Take Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 36 Twp. 10S Rge. 25 000000(W)  
Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner Empire Drilling Company  
Lease Name Kinderknecht Well No. 1  
Office Address 650 Fourth National Bank Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 19, 1962 19  
Application for plugging filed April 19, 1962 19  
Application for plugging approved April 19, 1962 19  
Plugging commenced April 19, 1962 19  
Plugging completed April 19, 1962 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4050 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Clay Shale	0	672'	8 5/8"	127'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug set at 540' with 20 sacks cement.  
Plug set at 150' with 20 sacks cement.  
Plug set at 35' with 10 sacks cement.

APR 30 1962  
04-30-1962  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Empire Drilling Company  
Address 650 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Dan J. Kornfeld (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
650 Fourth Nat'l Bank Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of April, 1962.

My commission expires October 21, 1962.  
Lucille H. Harr Notary Public.



15-065-00010-00-00

LOG

04-30-1962

COMPANY: Empire Drilling Company  
 CONTRACTOR: Empire Drilling Company  
 FARM: Kinderknecht # 1  
 LOCATION: SE SE SW of Section 36-10S-25W, Graham County, Kansas  
 COMMENCED: April 10, 1962 ELEVATION: 2436 KB  
 COMPLETED: April 19, 1962 POTENTIAL: D & A

0	to	672	Surface Clay-Shale
672	to	1350	Shale
1350	to	1800	Shale-Sand-Pyrite
1800	to	2083	Shale-Red Bed
2083	to	2120	Anhydrite
2120	to	2400	Shale-Shells
2400	to	2580	Shale-Pyrite
2580	to	2900	Shale-Shells
2900	to	2980	Lime
2980	to	3480	Lime-Shale
3480	to	3580	Shale
3580	to	3853	Lime-Shale
3853	to	3905	Lime
3905	to	3950	Lime-Chert
3950	to	4050	Lime
4050			Rotary Total Depth

SET: 127' of 8 5/8" casing with 75 sacks cement.

SAMPLE TOPS:

Anhydrite	2083	+353
Heebner	3752	-1316
Toronto	3773	-1337
Lansing	3788	-1352
Base Kansas City	4038	-1602
Rotary Total Depth	4050	

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Kinderknecht # 1, SE SE SW of Section 36-10S-25W, Graham County, Kansas, as reflected by the files of Empire Drilling Company.

Dan J. Kornfeld  
Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 30th day of April, 1962.

Lucille H. Harr  
Lucille H. Harr, Notary Public

My Commission expires October 21, 1962.