

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-193-20,596-00-00

LEASE NAME Hodges 'A'

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

330' Ft. from S Section Line

2970' Ft. from E Section Line

SEC. 2 TWP. 10S RGE. 33 (E) or (W)

COUNTY Thomas

Date Well Completed _____

Plugging Commenced 7-4-92

Plugging Completed 7-4-92

LEASE OPERATOR Thunderbird Drilling, Inc.

ADDRESS P.O. Box 780407, Wichita, KS 67278

PHONE#(316) 685-1441 OPERATORS LICENSE NO. 5131

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-4-92 (date)

by Dennis Hamil (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? _____

Producing Formation LKC, Marm., Miss. Depth to Top _____ Bottom _____ T.D. 4770'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 340' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Fill w/heavy mud; set 1st plug @ 2675'-2575' w/25 sx; 2nd plug @ 1750'-1350' w/100 sx; 3rd plug @ 355'-195' w/40 sx; 4th plug @ 40'-surface w/10 sx w/wiper plug; rathole 15 sx; 190 sx 60-40 posmix 6% gel 1/4# Flocel per sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Thunderbird Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801, Wichita, KS 67202



Angela Woodard
Notary Public

SUBSCRIBED AND SWORN TO before me this 9th day of July, 19 92

My Commission Expires: March 20, 1993

RECEIVED
STATE CORPORATION COMMISSION
07-22-1992
JUL 22 1992
CONSERVATION DIVISION
Wichita, Kansas