

STATE OF KANSAS  
 KANSAS CORPORATION COMMISSION  
 CONSERVATION DIVISION  
 130 South Market - Room 2078  
 Wichita, Ks. 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-193-20,631-00-00

LEASE NAME Schoenfeld

WELL NUMBER 12-6

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

2310 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 12 TWP. 10S RGE. 33 (W)

LEASE OPERATOR L. B. Industries

ADDRESS 12200 E. Briarwood Ave., Ste 250, Englewood, Co. 80112 COUNTY Thomas

PHONE# (303) 790-8340 OPERATORS LICENSE NO. 3680

Date Well Completed 04-15-95

Character of Well D & A

Plugging Commenced 04-14-95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 04-15-95

The plugging proposal was approved on 04-10-95 (date)

by Dennis Hammel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4870'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8 5/8"	8 its	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Fill w/heavy mud; 1st plug from 2650'-1550' w/25 sks, 2nd plug from 1900'-1500' w/ 100 sks, 3rd plug from 400'-240' w/40 sks, 4th plug from 40'-surface w/10 sks, 15 sks rathole, total 190 sks, 60/40 posmix, 6% gel, w/3# floeal per sk.

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Ste 801, Wichita, Ks 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. B. Industries

STATE OF Kansas COUNTY OF Sedgwick, ss.

(Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filled in the same are true and correct, so help me God.

(Signature) Jack K. Wharton 04 APR 24 1995

(Address) 150 N Main, Ste 801, Wichita, Ks 67202

SUBSCRIBED AND SWORN TO before me this 21<sup>st</sup> day of April 1995  
 SANDRA C. McCAIG  
 NOTARY PUBLIC  
 STATE OF KANSAS  
 My Comm. Exp. 1-31-98

1-31-98

Sandra C. McCaig  
 Notary Public

USE ONLY ONE SIDE OF EACH FORM