

15-193-20053-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Thomas County, Sec. 3 Twp. 10 Rge. (E) 34 (W)

Location as "NE/CNW/SW" or footage from lines C NW NE
F & M Oil Company

Lease Owner KRISS Well No. #1

Lease Name KRISS Office Address 603 Union Center, Wichita, Ks. 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 7 1974

Application for plugging filed (verbally) November 7 1974

Application for plugging approved (verbally) November 7 1974

Plugging commenced November 7 1974

Plugging completed November 7 1974

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Nichols

Producing formation Depth to top Bottom Total Depth of Well 4830 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	320'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st Plug Set @ 1750' with 70 sacks cement

2nd Plug Set @ 315' with 20 sacks cement

3rd Plug Set @ 40' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1974
11-14-1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Jerry A. Langrehr, Exec. V.P. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Jerry A. Langrehr

801 Union Center, Wichita, Kansas 67202 (Address)

November 19 74

Nancy E. Bledsoe
Nancy E. Bledsoe Notary Public.

April 8, 1978



15-193-20053-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	F & M Oil Company
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	KRISS #1
LOCATION:	C NW NE Sec. 3-10S-34W Thomas County, Kansas
GEOLOGIST:	R. D. Messinger
SPUD DATE:	October 27, 1974
COMPLETION DATE:	November 7, 1974

0	270	Surface soil and Sand
270	320	Shale
320	1370	Shale and Sand
1370	2183	Shale
2183	2216	Anhydrite
2216	2645	Shale and Sand
2645	3440	Shale
3440	4005	Lime and Shale
4005	4765	Lime
4765	4830	Lime and Shale
	4830	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1974
11-14-1974
CONSERVATION DIVISION
Wichita, Kansas

Drilled 322' of 12 1/4" surface hole. Ran 8 jts. of 8-5/8" used surface casing. Set @ 320' with 200 sacks Quickset Cement. Cement circulated. Plug was down @ 4:30 p.m., October 27, 1974.
D & A: 1st Plug set @ 1750' with 70 sacks; 2nd Plug set @ 315' with 20 sacks; 3rd Plug set @ 40' with 10 sacks; Plug was down @ 7:00 a.m. November 7, 1974

<u>SAMPLE TOPS:</u>		<u>ELEVATION:</u>
Anhydrite	2774 (+473)	3247 K.B.
B/Anhydrite	2807 (+440)	3245 D.F.
		3243 G.L.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the KRISS #1, C NW NE, Section 3-10S-34W, Thomas County, Kans.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
Jerry A. Langrehr
Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 13th day of November, 1974.

Nancy E. Bledsoe
Nancy E. Bledsoe - Notary Public

My Commission Expires:
April 8, 1978

