

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-193-20169-00-00

LEASE NAME Deloris #1

WELL NUMBER NW NW

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 5 TWP. 10 RGE. 34 (S) or (W)

COUNTY Thomas

Date Well Completed

Plugging Commenced 5/7/85

Plugging Completed 5/24/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Beren Corporation

ADDRESS 970 4th Finan. Ctr. Wichita, Ks. 67202

PHONE#(316) 265-3311 OPERATORS LICENSE NO. 5364

Character of Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4950'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	336'	none
				4 1/2"	4485'	2716'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged bottom with 4 sacks cement, sand to 4275' & 4 sacks cement. Shot pipe at 3035' & 2716'. Pulled 68 joints of pipe. Plugged well with 4 hulls, 40 gal, 8 5/8" plug, & 180 sacks cement.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) *R. Darrell Kelso*

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 31st day of May, 19 85

Irene Hoover

My Commission Expires:



Notary Public

STATE CORPORATION COMMISSION

JUN 03 1985
06-03-1985
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 08-84

DAILY DRILLING REPORT

15-193-20169-00-00/H.C.

PROSPECT Dolores YEAR 1978
 LEASE Dolores WELL NO. 1 WELL LOCATION NW NW (440-440) COUNTY Thomas STATE KS
 SITE LEASE DESCRIPTION Sec. 5-10S-34W CODE _____
 OPERATOR Beren Corporation ELEVATION: GR 3295
 CONTRACTOR Abercrombie DF _____
 GEOLOGIST Bob Lewellyn KB 3300
 DEVELOPMENT WELL. _____ PROSPECT TEST WELL XX NOTIFY Petroleum, Inc.
 OWNERSHIP 100% program 800 R.H. Garvey Building
300 West Douglas
Wichita, Kansas 67202
261-5427
 IDENTIFICATION test well

DST

8/15/78	4562'	#7	4460 - 95 ("L") 30-45-120-90 300' water 1275/1167 18/54 54/126
8/16/78	4650		
8/17/78	4790'		
8/18/78	4845'	#8	4566 - 4650 (Altamont and Upper Pawnee) 30-45-30-45 30' mud 843/699 54/63 63/72
8/21/78	4950' RTD		
LOG TOPS:		#9	4700 - 4790 (Cherokee and Johnson Zone) 30-45-60-60 1500' water SSO 1113/969 90/484 448/735
Anhydrite	2827 (+ 473)		
Base Anhydrite	2856		
Foraker	3647		
Wabaunsee	3742		
Tarkio	3831		
Elmont	3878		
Bern	3907		
Howard	3931		
Topeka	3956		
Heebner	4167 (- 867)	#10	4800 - 4845 (Cg1) 30-45-40-60 1475' water 1005/1085 54/430 448/690
Toronto	4191 (- 891)		
Lansing K.C.	4209 (- 909)		
Stark	4435 (-1135)		
Base K.C.	4511		
Marmaton	4521 (-1221)		
Pawnee	4624 (-1324)		
Fort Scott	4686 (-1386)		
Cherokee	4715 (-1415)		
Johnson Zone	4759 (-1459)		
Miss	4847 (-1547)		
L.T.D.	4949		

RECEIVED
STATE CORPORATION COMMISSION

MAY 10 1985

CONSERVATION DIVISION
Wichita, Kansas

Ran 113 joints of 4½" - 10½# casing. (Tally 4515.60'). Set at 4495'. Cemented with 200 sacks 60-40 posmix, 10% salt, 2% gel, 3/4 of 1% CFR-2. Job was complete at 3:15 p.m., 8-19-78.

To set 4½ at 4485'