


STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 800 Bitting Building
 Wichita, Kansas

OR
FORMATION PLUGGING RECORD Strike out upper line when reporting plugging off formations.

Ottawa County. Sec. 17 Twp. 11 Rge. (E) 2 (W)
 Location as "NE¼NW¼SW¼" or footage from lines. SE SE SE
 Lease Owner. Westgate-Greenland Oil Company
 Lease Name. Beverly Well No. 1
 Office Address. 1022 Union National Bank Bldg, Wichita 2, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) dry hole
 Date well completed. September 30, 1947 19.
 Application for plugging filed. September 30, 1947 19.
 Application for plugging approved. September 30, 1947 19.
 Plugging commenced. September 30, 1947 19.
 Plugging completed. September 30, 1947 19.
 Reason for abandonment of well or producing formation. dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production. 19.
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well. Ruel Durkee, Box 597, McPherson, Kansas
 Producing formation. Depth to top. Bottom. Total Depth of Well. 3646 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	161	8 5/8"	161	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole from 3646 to 160 feet with heavy mud. Set plug @ 160 feet.
 Used 15 sacks cement on top of plug and then
 Filled with heavy mud to 25'
 25' to cellar filled with 5 sacks cement.

10-11-1947

(If additional description is necessary, use BACK of this sheet)
 Correspondence regarding this well should be addressed to G. E. Bitler, c/o Westgate-Greenland Oil Company
 Address. 1022 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
 G. E. Bitler (employee of owner) or ~~operator~~ of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *G. E. Bitler*
 1022 Union National Bank Building, Wichita 2, Kans.
 (Address)

SUBSCRIBED AND SWORN to before me this 10th day of October, 1947.
Ether Wells
 Notary Public.

My commission expires May 25, 1949

17 11 2W
 137 15

15-143-00006-00-00

COMPANY : Westgate-Greenland Oil Company
CONTRACTOR : Jackson Drilling Corporation
FARM : Beverly #1
LOCATION : SE SE SE of 17-11-2W, Ottawa County, Kansas
COMMENCED : September 12, 1947
COMPLETED : September 30, 1947

0	to	161	Water sand-red bed and surface rock
161	to	365	Shale and lime rock
365	to	515	Lime and shale
515	to	791	Lime
791	to	942	Lime and shale
942	to	960	Shale
960	to	1445	Shale and lime
1445	to	1470	Lime
1470	to	1600	Lime and shale
1600	to	1660	Shale
1660	to	1735	Lime and shale
1735	to	1945	Lime
1945	to	2030	Lime and shale
2030	to	2095	Shale
2095	to	2155	Shale and lime
2155	to	2185	Shale and shells
2185	to	2215	Lime and shale
2215	to	2505	Lime
2505	to	2625	Lime and shale
2625	to	2785	Shale
2785	to	2801	Lime and chert
2801	to	2814	Lime
2814	to	2937	Lime and chert
2937	to	2985	Shale
2985	to	3038	Lime
3038	to	3165	Shale
3165	to	3258	Lime -Hunton
3258	to	3285	Shale and chert
3285	to	3396	Shale
3396	to	3425	Shale and chert
3425	to	3505	Lime
3505	to	3540	Sand and shale
3540	to	3566	Lime and shale
3566	to	3617	Simpson sand
3617	to	3646	Shale and Lime
		3646	T. D. Rotary

Set 161 feet of 8 5/8" surface pipe. Cemented with 125 sacks cement.

Tops. Mississippi 2723. Hunton 3142. Viola 3395. Smp Sd 3566.
Arbuckle Dolomite 3613.

Dry, plugged and abandoned.

C E R T I F I C A T E

I, L. C. Crowe, do hereby certify that the above and foregoing is a true and correct copy of log of the Beverly No. 1, Section 17-11-2W, Ottawa County, Kansas, as reflected by files of the Jackson Drilling Corporation.

L. C. Crowe

L. C. Crowe

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 7th day of October, 1947.

Esther Russell
Notary Public

My commission expires May 25, 1949.

PLUGGING
FILE SEC 17-11-2W
BOOK PAGE 137/15