

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Graham County, Sec. 31 Twp. 9 Rge. 23 (E) W (W)

Location as "NE/CNWKSWK" or footage from lines C S/2 SW 1/4 NE 1/4

Lease Owner D. G. Hansen

Lease Name Moore Well No. 1

Office Address Logan, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 7 1963

Application for plugging filed August 7 1963

Application for plugging approved August 7 1963

Plugging commenced August 7 1963

Plugging completed August 7 1963

Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4025 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	209.50	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 540'. Set plug. Put in 20 sacks cement. Filled hole with heavy mud to 200'. Set plug. Put in 1/2 sack hulls and 20 sacks cement. Filled hole with heavy mud to 40'. Set plug. Filled to top with 1/2 sack hulls and 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
8-19-63  
AUG 19 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.  
Address 107 Rule Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Jay H. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jay H. Galloway  
Jay H. Galloway 107 Rule Bldg.  
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of August, 1963

My commission expires May 20, 1967

Vicky Jacobs  
Notary Public.



WELL LOG

OPERATOR D. G. HANSEN SEC. 31-9-23W  
 WELL NAME MOORE #1 LOC. C S/2 SW/4 NE/4  
 TOTAL DEPTH 4025' COUNTY Graham  
 COMM. July 26 63 COMP. August 7, 1963 STATE Kansas  
 RIG NO. 1 ELEVATION 2449' K.B.  
 CASING: Set 209.50' (10 jts) 8-5/8" OD Surface casing PRODUCTION: Dry & Abandoned

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	209	Shale & Sand		
209	1610	Shale	500' - $\frac{1}{2}^{\circ}$	
1610	1805	Sand	1000' - $\frac{1}{2}^{\circ}$	
1805	2063	Red Bed & Shale		
2063	2105	Anhydrite		
2105	2110	Shale		
2110	2340	Shale & Shells		
2340	2490	Shells, Shale & Lime		
2490	3765	Lime & Shale	2500' - $\frac{3}{4}^{\circ}$	
3765	4025	Lime	3000' - $\frac{1}{2}^{\circ}$	DST #1 3812' - 3838'
			3500' - $\frac{3}{4}^{\circ}$	DST #2 3851' - 3870'
				DST #3 3940' - 3954'
				DST #4 3952' - 3976'

RECEIVED  
 STATE CORPORATION COMMISSION

AUG 19 1963

CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 COUNTY OF SEDGWICK ) SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Ray H. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 9th day of August, 1963.

My commission expires  
 May 20, 1967

Vicky Jacobs  
 Vicky Jacobs - Notary Public