


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 31 Twp. 9 Rge. 23 (E) (W)x

Location as "NE/CNWxSWx" or footage from lines SE SW NW  
Lease Owner Imperial Oil of Kansas, Inc.  
Lease Name Cameron Well No. #1  
Office Address 2318 Washington, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 7-20-65 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 7-21-65 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4050' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged 4 1/2" casing from top to bottom with 10 sacks cement, followed with 24 sacks gel mix 2 1/2 to 1. Displaced with 40 sacks cement. Mixed and pumped 6 sacks gel and 25 sacks cement between 8 5/8" and 4 1/2" casing. Cement at base of cellar in both casing.

RECEIVED  
STATE CORPORATION COMMISSION  
7-23-65  
JUL 23 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.  
Address Box 364, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer, Inc.  
Box 364, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of July, 19 65

My commission expires 24 October 1968

Sidney D. Miller  
Notary Public.

DRILLER'S LOG

Imperial Oil Company  
780 Fourth National Building  
Wichita, Kansas

Cameron No. 1  
SE SW NW Sec. 31-9S-23W  
Graham County, Kansas

Total Depth: 4050 ft.

Elevation: K3 2480 ft.

Commenced: 1-11-65

Completed: 1-20-65

Contractor: Imperial Oil of Kansas, Inc.  
Rig #2

Casing Record: Set 8-5/8" surface casing at 229 feet with 175 sacks cement. Set 4-1/2" casing at 4049 feet and cemented with 150 sacks No. 1 Posmix, salt added. Cemented Dakota Sand with 300 sacks.

Figures indicate bottom of formations:

Shale-Sand	140'
Shale-shells	960'
Shale	1638'
Dakota Sand	1850'
Shale Red Bed	2100'
Anhydrite	2137'
Shale-shells	2350'
Shale-lime	2572'
Lime-shale	3814'
Lime	4050'
RTD	4050'

**RECEIVED**  
STATE CORPORATION COMMISSION

AUG 6 - 1965

CONSERVATION DIVISION  
Wichita, Kansas

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

By Robert L. Williams, Jr.  
Robert L. Williams, Jr.

Subscribed and sworn to before me this 11th day of February, 1965.

My Commission Expires July 5, 1966.

Bette J. Silcott  
Bette J. Silcott