

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,017-0000

LEASE NAME Justus #1

WELL NUMBER _____

SPOT LOCATION NE SW NW

SEC. 32 TWP. 9S RGE. 23W(E) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 1/6/86

Plugging Completed 1/9/86

LEASE OPERATOR Robert W. Myers, Jr.

ADDRESS 11945 Forestwood Dr. Dallas, Tx. 75244

PHONE # (214) 960-1332 OPERATORS LICENSE NO. 9542

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	342'	none
				4 1/2"	4049'	1819'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3930' & 4 sacks cement. Shot pipe at 2514', 2031', and 1819'. Pulled 43 joints of pipe. Pumped well with 3 hulls, 20 gel, 100 cement with 1 hull, 20 gel, released plug, & 80 sacks 60/40 poz 6% gel 3% c.c.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 13th day of January, 1986



My Commission expires: _____

RECEIVED
STATE CORPORATION COMMISSION
Notary Public
Irene Hoover

1-15-86
JAN 15 1986

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 01-84