

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Graham County. Sec. 33 Twp. 9 Rge. 23 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW NW NW

Lease Owner Harry Gore

Lease Name Justus Well No. 1

Office Address 400 Brown Bldg., Wichita, Kas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-30-51 19

Application for plugging filed 9-6-51 19

Application for plugging approved Verbal 19

Plugging commenced 8-31-51 19


Plugging completed 8-31-51 19

Reason for abandonment of well or producing formation

Well was dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	171	8 5/8"	171	(0)
					4505'	T.D.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with mud - 4505' Plugged hole with 15 sacks of cement at 160' and 10 Sacks cement and one half sack of hulls from 15' to top of hole

RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company
Address 1121 Union Natl Bank Bldg., Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dan J. Kornfeld (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Empire Drilling Company

By Dan J. Kornfeld (Address)

SUBSCRIBED AND SWORN to before me this 8th day of September, 1951

Charlotte Fletcher Notary Public.

My commission expires June 7, 1952

PLUGGING
FILE SEC 33-T-9-R-230
BOOK PAGE 67 LINE 15

COMPANY: Harry Gore
 CONTRACTOR: Empire Drilling Company
 FARM: Justus No. 1
 LOCATION: NW NW NW Sec. 33-9-23W
 Graham County, Kansas
 COMMENCED: August 11th, 1951
 COMPLETED: August 30th, 1951

0	to-	90	Shale
90	to	140	Sand & Shells
140	to	195	Shale & Shells
195	to	325	Shale & Shells
325	to	1220	Shale & Shells
1220	to	1540	Shale & Shells
1540	to	1665	Shale & Shells
1665	to	1810	Shale & Shells
1810	to	2115	Shells & Shale
2115	to	2215	Anhydrite
2215	to	2370	Shale & Lime
2370	to	2535	Lime
2535	to	2565	Lime
2565	to	2656	Lime, Shales
2656	to	2720	Lime & Shale
2720	to	2920	Shale & Lime
2920	to	3195	Shale & Lime
3195	to	3325	Shale & Lime
3325	to	3420	Shale & Lime
3420	to	3480	Lime
3480	to	3655	Lime & Shale
3655	to	3845	Lime & Shale
3845	to	3881	Lime
3881	to	4072	Shale & Lime
4072	to	4110	Conglomerate
4110	to	4275	Lime & Shale
4275	to	4318	Conglomerate
4318	to	4375	Cherty Conglomerate
4375	to	4437	Conglomerate
4437	to	4453	Cherty Conglomerate
4453	to	4480	Arbuckle
4480	to	4505	Arbuckle T.D. Rotary

Set. 171' 8 5/8" Surface Pipe. Cemented with 135 Sacks Cement.
 Ran Schlumber Electric Log at 4505'
 Tops:
 Topeka 3575' Heebner Shale 3799' Lansing K.C. 3833' Base K.C. 4068'
 Marmaton Cong. 4175' Cherty Cong. 4292' Arbuckle 4453' T.D. 4505'
 All depths taken from Kelly Bushings 3' above derrick floor.
 Elevation 2478 D.F.

DRY

C E R T I F I C A T E

I, Dan J. Kornfeld do hereby certify that the above and foregoing is a true and correct copy of the log of the Justus No.1 Sec. 33-9-23W Graham County, Kansas as reflected by files of the Empire Drilling Company

33 9 23W
 107 15

Dan J. Kornfeld
 Dan J. Kornfeld

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas this 6th Day of September, 1951
 My commission expires Dec. 22, 1954.
Evelyn V. North
 Notary Public