

15-065-02661-0000

Company **Harvey Gore**

Sec. 34 T. 9 R. 23

Loc. SE NE SE

Farm **Law**

No. 3

County **Graham County, Kansas**

Total Depth **4235'**

Comm. **6-11-51**

Comp. **6-24-51**

Shot or Treated


Contractor **Veeder Supply Company**

Drilled with **Big - D**

Issued

No. of Days - **14**

No. of Pits -



Casing

20 in.	10 in
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/8

Run **225'** of **6-5/8"** Casing Cemented with **150** sacks cement.

Elevation **2456 KB**

Production

Figures Indicate Bottom of Formation

Surface Soil	0	40	40	<u>Tops:</u>	
Shale	40	60	20	Topoka	- 3491
Sand	60	100	40	Heobner Shale	- 3708
Shale Sand	100	175	75	Bodge Line	- 3730
Shale	175	220	45	Kansing F.G.	- 3741
Shale Shells	220	1020	800	Base K.G.	- 3968
Sand Shale	1020	1140	120	Marion Conglomerate	- 4065
Shale Shells	1140	1170	30	Marion Sand	- 4110-4116
Shale Shells Sand	1170	1550	380	Cherty Conglomerate	- 4159
Sand Shale	1550	1730	230	Arinackie	- 4210
Shale Shells	1730	2020	240		
Anhydrite	2020	2068	48		
Shale Shells	2068	2120	52		
Shale Shells Red Rock	2120	2450	330		
Shale Shells	2450	2500	50		
Lime Shale Some Salt	2500	2585	85		
Lime Shale	2585	2760	175		
Lime	2760	2810	50		
Lime Shale	2810	3745	935		
Lime	3745	3930	235		
Lime Shale	3930	4055	75		
Lime Shale Cherty	4055	4095	40		
Conglomerate	4095	4130	35		
Conglomerate Cherty	4130	4210	80		
Lime	4210	4235	25		
Total Depth	4235'				

Plugged at 200 feet with 15 sacks cement.
Plugged at 40 feet with 10 sacks cement.

STATE

JUN 30 1951

CONSULTING ENGINEER
Wichita, Kansas

PLUGGING
FILE SEC 34T 9 R 23W
BOOK PAGE 90 LINE 29