



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1969
CONSERVATION DIVISION
Wichita, Kansas
10-24-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-19170-00-00

Dear Sir:

Mr. Walter Voth of Knight Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Ivy Oil Company.

Complete Address: Box #86, Plainville, Kansas.

Lease Name: John Johnson Well No. 1

Location: SE-SE Sec. 10 Twp. 10 Rge. (E)(W) 23

County: Graham Total Depth 3920' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Voth was instructed to plug the well as follows:

214'--8 5/8" Surface casing, cement circulated ~~WEEK~~.

3917'--4 1/2" Production casing cemented on bottom with 100 Sx. Top perforations @ 3676'. DV tool set @ 1744' with 100 Bbl. Chem-Pak.

Sand well back to 3650' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 130 Sx. cement staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent