



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-065-30204-00-00

RECEIVED
MAR 31 1966
03-31-1966
Conservation Division
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil of Kansas, Incorporated,

Complete Address: Box #784, Great Bend, Kansas.

Lease Name: Johnson Well No. 1

Location: SE-NE-NW Sec. 10 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3935 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Unruh was instructed to plug the well as follows:

210'--8 5/8" Surface pipe, cement circulated with 150 Sx.
3934'--4 1/2" pproduction casing cemented with 150 Sx. Well
plugged back to 3919'. Top perforations from 3878' to 3882'.

Sand well back to 3860' and set 3 Sx. cement with dump bailer.

Pull 4 1/2" casing and squeeze well with 20 Sx. gel and 50 Sx.
cement.

Very truly yours,

H. L. Dickels
Conservation Division Agent