

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-065-30162-00-00

10-17-1964

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Roy Cook of Imperial Oil Co., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Company,

Complete Address: 780 4th National Bank Bldg., Wichita, Kansas.

Lease Name: Johnson Well No. 2

Location: NE-NE-SW Sec. 10 Twp. 10 Rge. (E)(W) 23

County Graham Total Depth 3900 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

207'--8 5/8" Surface pipe, cement circulated with 135 Sx.

Circulate hole with heavy mud, set plug @ 600' and 20 Sx. cement.

" " 200' with 1/4 sk. hulls & 20 Sx. cement.  
" " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

*W. L. Nichols*

Conservation Division Agent