

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-065-03127-00-00

DEC 14 1964
12-14-1964
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company,

Complete Address: P.O. Box #649, McCook, Nebraska.

Lease Name: Griffith Well No. A-1

Location: SW-SW-SW Sec. 11 Twp. 10 Rge. (E)(W)23

County Graham Original TD 3961
PB- Total Depth 3690 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

247'--8 5/8" Surface pipe, cement circulated
3960'--5 1/2" Casing cemented. Well plugged back to 3690.
Top perforations from 3681' to 3687'.

Sand well back to 3650' and set 5 Sx. cement with dump bailer.

Pull 5 1/2" casing and squeeze well with 30 sacks gel followed with
75 sacks cement.

Very truly yours,

W. L. Nichols
Conservation Division Agent