

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027

3830 S. Meridian

WICHITA, KANSAS 67217

15-065-01884-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1974
CONSERVATION DIVISION
Wichita, Kansas
10-21-1974

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Charlie Crow of Charlie Crow Drilling Company has this date requested permission to plug the following described well:

Mr. Crow guarantees payment of the plugging fee.

Operator's full Name: Herman George Kaiser,

Complete Address: 4120 E. 51st Street, Tulsa, Oklahoma.

Lease Name: Conness Well No. A-2

Location: W/2-W/2-SW Sec. 23 Twp. 10 Rge. (E)(W) 23

County: Graham Total Depth 3878' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Crow was instructed to plug the well as follows:

201'--8 5/8" Surface casing, cement circulated with 150 Sx.
3876'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 3846'. Top perforations from 3715' to 3810'.

Push plug to 3650', sand back to 3625' and set 4 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 150 Cu. Ft. cement and 25 sacks gel, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent