



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

13-065-00601-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 21 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 10-21-1968

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of Southwest Csg. Pulling Co. Inc has this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Herman Geo. Kaiser,

Complete Address: 909 Palace Building, Tulsa, Oklahoma.

Lease Name: Conness Well No. A-1

Location: SW-SW-SW Sec. 23 Twp. 10 Rge. (E)(W) 23

County: Graham Total Depth 3870 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Clark was instructed to plug the well as follows:

182'--8 5/8" Surface casing, cement circulated with 150 Sx.
3868'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 3833'. Top perforations @ 3712'.

Push plug to 3700', build sand bridge and set 5 Sx. cement with dump bailer.
Pull 5 1/2" casing and squeeze well with 30 sacks gel plus 5 sacks hulls and 130 Sx. cement staged.

Very truly yours,

W. L. Nichols
 Conservation Division Agent