



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 15 1971

CONSERVATION DIVISION
Wichita, Kansas

07-15-1971

15-065 - 20468-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ed. Weiler of Shields Drlg. Co., Inc. has this

date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Black Petroleum, Incorporated,

Complete Address: 445 O. W. Garvey Building, Wichita, Kansas.

Lease Name: McVey Well No. 1

Location: SW-NW-NW Sec. 24 Twp. 10 Rge. (E)(W) 23

County: Graham Total Depth 4000' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Weiler was instructed to plug the well as follows:

200'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 775'.

Circulate hole with heavy mud. Pull DP to 1000' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent