



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 28 1968
 CONSERVATION DIVISION
 Wichita, Kansas

10-28-1968

15-065-19171-00-00

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Wilber Crandall of Knight Casing Pulling Co. Inc. has this date requested permission to plug the following described well:

Mr. Crandall guarantees payment of the plugging fee.

Operator's full Name: Ivy Oil Company,

Complete Address: Box #86, Plainville, Kansas.

Lease Name: McCall Well No. B-2

Location: SE-SE-NW Sec. 25 Twp. 10 Rge. (E)(W) 23

County: Graham Total Depth 4040 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Crandall was instructed to plug the well as follows:

200'--8 5/8" Surface casing, cenebt circulated with 150 Sx.
3770'--5 1/2" Production casing, cemented on bottom with 75 Sx. Well plugged back to 3731'. Top perforations @ 3599'.

Push plug to 3575' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 30 sacks gel plus 5 sacks hulls in initial gel and 130 Sx. cement staged.

Very truly yours,

H. L. Nichols
 Conservation Division Agent