



15-065-03186-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1967
03-22-1967
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Herman Fell hoeltesof Ivy Oil Company has this
date requested permission to plug the following described well:

Mr. Fellhoelter guarantees payment of the plugging fee.

Operator's full Name: Ivy Oil Company,

Complete Address: Box # 86, Plainville, Kansas.

Lease Name: Griffith Well No. 1

Location: SW-SW-NE Sec. 25 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 4052 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Fellhoelter was instructed to plug the well as follows:

194'--8 5/8" Surface pipe, cement circulated with 200 Sx.

3830'--5 1/2" Production casing cemented with 100 Sx. Top perfor-
ations from 3611' to 3616'.

Sand well back to 3600' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" to 700' and circulate heavy gel mud. Pull 5 1/2" to 600'
and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 180' and dis-
place 20 Sx. cement thru 5 1/2". Pull 5 1/2", set rock bridge @ 30'
and 10 Sx. cement to bottom of cellar.

Very truly yours,

H. L. Nichols
Conservation Division Agent