



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 28 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

15-065-00443-00-00

10-28-1968

Dear Sir:

Mr. Wilber Crandall of Knight Casing Pulling Co. Inc. has this date requested permission to plug the following described well:

Mr. Crandall guarantees payment of the plugging fee.

Operator's full Name: Ivy Oil Company,

Complete Address: Box #86, Plainville, Kansas.

Lease Name: McCall Well No. B-1

Location: NE-NE-SW Sec. 25 Twp. 10 Rge. (E)(W) 23

County: Graham Total Depth 4145 Oil Well

Gas Well      Input Well      SWD Well X D & A      Lost Hole     

Mr. Crandall was instructed to plug the well as follows:

208'--8 5/8" Surface casing, cement circulated with 150 Sx.  
3845'--5 1/2" casing cemented on bottom with 75 Sx. Well plugged back to 3830'  
Top perforations @ 3596'.

Push plug to 3575' and set 5 Sx. cement with dump bailer. Pull 5 1/2"  
casing and squeeze well with 30 Sx. gel with 5 sacks hulls in initial gel  
and 130 Sx. cement staged.

Very truly yours,

Conservation Division Agent