

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-193-20053-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1974
11-15-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Don Favinger of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: F & M Oil Company, Incorporated,

Complete Address: 603 Union Center, Wichita, Kansas.

Lease Name: Kriss Well No. 1

Location: CNW-NE Sec. 3 Twp. 10 Rge. (E)(W) 34

County: Thomas Total Depth 4850' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Favinger was instructed to plug the well as follows:

312'--8 5/8" Surface casing, cement circulated with 210 Sx.
Top of Dakota section @ 1525'.

Circulate hole with heavy mud. Pull DP to 1750' and displace 110 Cu. Ft. cement thru DP. Pull DP to 315' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

A. L. Nichols
Conservation Division Agent