

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-193-20,596-00-00 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Thunderbird Drilling, Inc. OPERATOR'S LICENSE NO. 5131

ADDRESS P.O. Box 780407, Wichita, KS 67278 PHONE # (316) 685-1441

LEASE (FARM) Hodges 'A' WELL NO. #1 WELL LOCATION SE SE SW COUNTY Thomas

SEC. 2 TWP. 10S RGE. 33 (E) or (W) TOTAL DEPTH 4770' PLUG BACK TD

Check One:

OIL WELL GAS WELL D & A X SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8" SET AT 340' CEMENTED WITH 60-40 posmix-250 sx SACKS

CASING SIZE SET AT CEMENTED WITH SACKS

PERFORATED AT

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2675' w/25 sx; 2nd plug @

1750' w/100 sx; 3rd plug @ 355' w/40 sx; 4th plug @ 40' w/10 sx w/wiper plug; rathole 15

sx; 190 sx 60-40 posmix 6% gel 1/4# Flocel per sx.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED? No

(If not explain.) Sent to Operator to complete.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 6:30 a.m. 7-4-92

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # (913) 674-5768

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie RTD, Inc. LICENSE NO. 30684

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Lehar
(Operator or Agent)

DATE: July 9, 1992

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
RECEIVED
07-22-1992
JUL 22 1992