

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-193-20,500-00-00 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Rine Exploration Company OPERATOR'S LICENSE NO. 5020

ADDRESS 300 W. Douglas, Suite 645, Wichita, KS 67202 PHONE # (316) 262-5418

LEASE (FARM) Carpenter WELL NO. 1-5 WELL LOCATION NE NW NE COUNTY Thomas

SEC. 5 TWP. 10S RGE. 33 ~~(E) (W)~~ TOTAL DEPTH 4780' PLUG BACK TD

Check One:

OIL WELL GAS WELL D & A X SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8" SET AT 327' CEMENTED WITH 200 SACKS

CASING SIZE SET AT CEMENTED WITH SACKS

PERFORATED AT

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Circulate heavy mud in hole. 1st plug at 2730'-25 sx. 2nd plug at 1775'-100 sx. 3rd plug at 375'-40 sx. 4th plug at 40'-10 sx. Rathole-15 sx. All cement 60/40 pozmix, 6% gel, 50# Cello Flake

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? No
(If not explain.) Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 12:00 midnight on 01-21-90

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # (913) 674-5768

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Wharton
(Operator or Agent)

DATE: 02-06-90

02
FEB 07-1990
7 1990
COM. DIVISION
Kansas