

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-193-20,631-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR L. B. Industries KCC LICENSE # 3680

(owner/company name) (operator's)

ADDRESS 12200 E. Briarwood Ave., Ste 250 CITY Englewood

STATE Colorado ZIP CODE 80112-6702 CONTACT PHONE # (303) 790-8340

LEASE Schoenfeld WELL# 12-6 SEC. 12 T. 10S R. 33 (~~East~~/West)

SW SE NW SPOT LOCATION/OOOO COUNTY Thomas

2310 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1650 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 358.23' CEMENTED WITH 225 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 3110/3115' T.D. 4870' PBTD _____ ANHYDRITE DEPTH 2628'-2656'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; 1st plug @ 2650' w/25 sks, 2nd plug @ 1900' w/100 sks, 3rd plug @ 400' w/40 sks, 4th plug @ 40' w/10 sks, 15 sks rathole, total 190 sks, 60/40 posmix, 6% gel, w/1# floseal per sk.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Tony Martin PHONE# () 316-262-1841

ADDRESS 150 N. Main Suite 801 City/State Wichita, Ks. 67202

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684

(company name) (contractor's)

ADDRESS 150 N. Main, Ste 801, Wichita, Ks. 67202 PHONE # () 316-262-1841

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 04-14-95 5:00 p.m.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 04-21-95 AUTHORIZED OPERATOR/AGENT: Jack K. Wharton

(signature) Vice President

RECEIVED
KANSAS CORPORATION COMMISSION
APR 24 1995
04-24-1995