

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-03271-00-00  
Spot: CSWNESE Sec/Twnshp/Rge: 36-9S-23W  
1650 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: VESPER Well Number: 2  
County: GRAHAM Total Vertical Depth: 4115 feet

Operator License No.: 31274  
Op Name: HRBEK, R.L.  
Address: RR 1, BOX 11  
MERINO, CO 80741

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 253  
Production: Size 4.5 feet: 4010  
Liner: Size feet:

*3133.74*

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/23/2001 1:00 PM  
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.  
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed  
Plugging  
Method:

Order 8 yards Redi-Mix - 6 sxs common cement - sand.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 04/23/2001 2:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 253' cwc. 4 1/2" set at 4010' cement N/A.  
Two stage N/A.  
Cement in 8 5/8" annulus at surface Could not pull pipe.  
Fluid level near bottom.  
Filled 4 1/2" with 8 yards Redi-Mix (10 yards by yield).  
Prod Perfs 3860' - 3866'.  
Plug complete.

INVOICED

DATE 5-10-01

WV. NO. 2001061792

KANSAS CORPORATION  
5-10-01  
MAY 10 2001

CONSERVATION DIV.

Remarks: LEASE ALSO KNOWN AS VESPER UNIT #5-2

Plugged through: CSG

District: 04

Signed Carl Goodrow

(TECHNICIAN)

PETROLEUM, INC

5-2

#2 VESPER

36-9-23W

SW NE SE

Contr. GARVEY DRLG CO

GRAHAM County

E 2415 RB Comm. Comp. 11-15-57 IP

160 BOPD/LANS

PHY POT

Tops	Depth	Datum
ANH	1965	450
HEEB	3650	-1235
TOR	3671	-1256
LANS	3684	-1269
B/KC	3914	-1499
TD	4115	-1700

Casing

8" 253

4" 4010

DST 3680-3780/1 HR, 715' MDY W, BHP 1025#

DST 3779-3855/1 HR, 40' V SL O & GCW,

BHP 907#

DST 3850-90/1 HR, G/25", 2760' GSY O,

BHP 1140#

DST 3872-3920/1 HR, 300' O, 30' HOCM,

BHP 1160#

CO 3943: 12/3901-04: ACID 1000: 18 BOPH,

NW/3 HRS: PLUG 3895: 12/3882-86: PLUG

3875, SSO: 24/3860-66: ACID 2500: 20 BOPH/

2 HRS: NW

VESPER POOL


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

INDEX