

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03272-00-01
Spot: NWNWSE Sec/Twnshp/Rge: 36-9S-23W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: VESPER LKC Unit Well Number: 5-3
County: GRAHAM Total Vertical Depth: 3961 feet

Operator License No.: 31274
Op Name: HRBEK, R.L.
Address: RR 1, BOX 11
MERINO, CO 80741

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 252
Production: Size 5.5 feet: 3959
Liner: Size _____ feet:

\$128.73

Well Type: EOR UIC Docket No: E10172.7 Date/Time to Plug: 04/20/2001 1:00 PM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed
Plugging
Method:

Order 10 years Redi-Mix - common cement and sand.

Plugging Proposal Received By: CARL GOODROW WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/20/2001 2:30 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 252' w/200 sxs cwc. 5 1/2" set at 3959' w/100 sxs.
Port collar at 1991' cwc 500 sxs.
Prod. Perf 3843' - 3883'.
Filled hole with 10 yards and Redi-Mix.
Plug complete.
Fluid Level at bottom of hole.

INVOICED

DATE 5-11-01
BILL NO. 2001061795

STATE CORPORATION COMMISSION
5-11-01
MAY 11 2001

Remarks: LEASE ALSO KNOWN AS VESPER #3.

Plugged through: CSG

District: 04

BOB

Signed

Carl Goodrow

(TECHNICIAN)

PETROLEUM, INC

5-3

#3

VESPER

36-9-23W
NW NW SE

Contr. GARVEY DRLG

GRAHAM

County

E 2415RB Comm. 9-17-57 Comp. 11-29-57 IP 123 BOPD

Tops	Depth	Datum
ANH	1965	450
TOP	3425	-1010
HEEB	3618	-1233
TOR	3671	-1256
LANS	3683	-1268
B/KC	3911	-1496
TD	3961	-1546

Casing
 8" 252
 5" 3959
 DST 3677-3780/1 HR, 860' GC WTRY MUD,
 BHP 1000#
 DST 3778-3850/1 HR, G/50", 2160' CL GSY
 O, 320' FROG O, BHP 1160#
 DST 3832-50/1 HR, 1980' CL GSY O, 780'
 B, BHP 1140#
 DST 3850-87/1 HR, G/12", 3550' CL O, BHP
 1200#
 CO 3961, 16/3879-83: 1 G OPH, NATL: ACID
 2500# 16/3859-63: SWB 28 BOPH, NW: PLUG
 3854: 16/3843-47: SWB
 24 BOPH, NATL: PLUG 3820
 16/3770-74: SWB 3 BW,
 NATL: ACID 500: SWB 10
 BOPH, 88% W: CO 3780:
 RE PERF 3770, NS: CO 3914

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Handwritten mark