

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-00998-00-01  
Spot: NENESE Sec/Twnshp/Rge: 36-9S-23W  
2310 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: VESPER LKC Unit Well Number: 5-1  
County: GRAHAM Total Vertical Depth: 4180 feet

Operator License No.: 31274  
Op Name: HRBEK, R.L.  
Address: RR 1, BOX 11  
MERINO, CO 80741

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 245  
Production: Size 5.5 feet: 3980  
Liner: Size feet:

\$135.85

Well Type: EOR UIC Docket No: E10172.1 Date/Time to Plug: 04/20/2001 10:00 AM

Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.

Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 8 yards Redi-Mix - common cement and sand.

Plugging Proposal Received By: CARL GOODROW  
Date/Time Plugging Completed: 04/20/2001 12:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 245' cwc. 5 1/2" set at 3980'.  
Port collar N/A - 5 1/2" cemented to surface.  
Prod Perfs 3849' - 3851'.  
Fluid Level near bottom of hole.  
Filled 5 1/2" with 8 yards Redi-Mix - 10 yards by yield.  
Plug complete.

INVOICE  
DATE 5-29-01  
NO. 2001061842

KANSAS CORPORATION COMMISSION  
5-22-01  
MAY 22 2001  
CONSERVATION DIVISION

Remarks: LEASE ALSO KNOWN AS VESPER #1.

Plugged through: CSG

District: 04

Signed Carl Goodrow  
(TECHNICIAN)

JD

PETROLEUM, INC

S-1

#1 VESPER

36-9-23W

NE NE SE

Contr. GARVEY DRLG

GRAHAM County

E 2387RB Comm.

Comp. 8-2-57

IP 200 BOPD/LANS

PHY. POT

| Tops | Depth | Datum |
|------|-------|-------|
| ANH  | 1925  | 462   |
| HEEB | 3615  | -1228 |
| TOR  | 3636  | -1249 |
| LANS | 3650  | -1263 |
| B/KC | 3875  | -1488 |
| ARB  | 4148  | -1761 |
| TD   | 4180  | -1793 |

Casing  
 8" 215  
 5" 3980  
 DST 3623-95/1 HR, 200' WTRY M, BHP 1025#  
 DST 3695-3750/1 HR, 20' O SPK M, 42' M,  
 BHP 1000#  
 DST 3750-3840/1 HR, G/50", 70' OCM, 370'  
 FROGGY O, 3100' FR O; BHP 1360#  
 DST 3822-40/15", 1900' FR O, 60' OCM,  
 BHP 1260#  
 DST 3840-90/1 HR, 65' OCM, 30' OIL, BHP  
 480#  
 DST 3998-4065/1 HR, 40' M, BHP 300#  
 PERF 8/3849-51, ACID 1000: TST 14 BFPH

|  |  |  |
|--|--|--|
|  |  |  |
|  |  |  |
|  |  |  |

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS