

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03262-00-00
Spot: CE2E2NW , Sec/Twnshp/Rge: 36-9S-23W
3960 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: RICE A Well Number: 3
County: GRAHAM Total Vertical Depth: 3917 feet

Operator License No.: 31274
Op Name: HRBEK, R.L.
Address: RR 1, BOX 11
MERINO, CO 80741

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 255
Production: Size 5.5 feet: 3916
Liner: Size feet:

\$ 127.30

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/23/2001 2:00 PM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 8 yards Redi-Mix - 6 sxs common cement - sand.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/23/2001 3:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 255' cwc. 5 1/2" set at 3916' - cement N/A.
Two stage N/A cement near surface in 8 5/8" annulus.
Fluid level near bottom.
Filled 5 1/2" with 8 yards Redi-Mix (10 yards by yield).
Prod. Perfs 3835' - 3841'.
Plug complete.
Note: Application may have been made for an injection well, but never used. Well was oil producer when plugged.

INVOICE
DATE 5-10-01
TRF. NO. 2001061792
KANSAS CORPORATION COMMISSION
5-10-01
MAY 10 2001
CONSERVATION DIVISION

Remarks: LEASE ALSO KNOWN AS VESPER UNIT #1-3.

Plugged through: CSG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

CHAMPLIN OIL & REFG

1-3

#3

RICE 1A'

36-9-23W
E2 E2-NW

Contr. ARMER DRLG

GRAHAM

County

E 2395

Comm. 1-21-58

Comp. 2-28-58

IP 170 BOPD

PHY POT

Tops	Depth	Datum
HEEB	3643	-1248
TOR	3668	-1273
LANS	3678	-1283
B/KC	3904	-1509
TD.	3917	-1522

Casing

8" 255

5" 3916

DST 3825-46/2 HR, 970' OIL,

BHP 640#

DST 3845-66/2 HR, 17' MUD,

BHP 0#

PERF 3835-41: ACID 2500: PMP

130 BO,NW/24 HRS

VESPER POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS