

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03268-00-00
Spot: CW2W2NE, Sec/Twnshp/Rge: 36-9S-23W
3960 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: LACERTE C Well Number: 6
County: GRAHAM Total Vertical Depth: 4085 feet

Operator License No.: 31274
Op Name: HRBEK, R.L.
Address: RR 1, BOX 11
MERINO, CO 80741

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 268
Production: Size 4.5 feet: 4000
Liner: Size _____ feet:

\$132.76

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/23/2001 3:00 PM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 8 yards Redi-Mix - 6 sxs common cement - sand.

Plugging Proposal Received By: CARL GOODROW WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/23/2001 4:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 268' cwc. 4 1/2" set at 4000' cmt N/A.
Two stage N/A - cement at surface in 8 5/8" annulus.
Prod Perfs 3806' - 3890'.
Fluid level at 3000'.
Filled 4 1/2" with 8 yards Redi-Mix (10 yards by yield).
Plug complete.

INVOICED

DATE 5-10-01
INV. NO. 2001061792

RECEIVED
KANSAS CORPORATION COMMISSION
5-10-01
MAY 10 2001

CONSERVATION DIVISION

Remarks: LEASE ALSO KNOWN AS VESPER UNIT #2-6.

Plugged through: CSG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

APR 30 2001

PETROLEUM, INC

2-6

#6 LACERTE 'C'

36-9-23W

W2 W2 NE

Contr. GARVEY DRLG CO

GRAHAM County

E 2394RB Comm. 12-23-57 Comp. 5-16-58

IP 57 BOPD

PHY POT.

Tops	Depth	Datum
ANH	1965	429
HEEB	3636	-1242
TOR	3655	-1261
LANS	3669	-1275
TD	4085	-1691

Casing
 8" 268
 4" 4000
 DST 3792-3822/1 HR, 900' GIP, 30' O & GCM, 60' HO & GCM, 120' FROG O, BHP 900#
 DST 3822-42/1 HR, G/50", 2500' CL GSY O, BHP 775#
 DST 3843-63/1 HR, G/35", 1680' FR O, BHP 675#
 DST 3863-3910/1 HR, 120' O & GCM, BHP 1000#
 GO 3924: PERF 6/3806-09: 12/3828-34: 8/3842-46: 8/3868-72: 8/3886-90: SWB 2 1/2
 VESPER POOL
 80PH, NATL: ACID
 1500: 24 BFPH, 3%

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS