

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03266-00-00
Spot: CNWSENE Sec/Twnshp/Rge: 36-9S-23W
3630 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: LACERTE C Well Number: 4
County: GRAHAM Total Vertical Depth: 4080 feet

Operator License No.: 31274
Op Name: HRBEK, R.L.
Address: RR 1, BOX 11
MERINO, CO 80741

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 236
Production: Size 4.5 feet: 3970
Liner: Size feet:

\$132.60

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/23/2001 4:00 PM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 8 yards Redi-Mix - 6 sxs common cement-sand/yard.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/23/2001 5:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 236' cwc. 4 1/2" set at 3970' cmt N/A.
Two stage N/A - cement at surface in 8 5/8" annulus.
Prod. Perf 3804' - 3829'.
Fluid level at bottom.
Filled 4 1/2" with 8 yards Redi-Mix (10 yards by yield)
Plug complete.

INVOICED
DATE 5-10-01
INV. NO. 2001061792
KANSAS CORPORATION COMMISSION
5-10-01
MAY 10 2001
CONSERVATION DIVISION

Remarks: LEASE ALSO KNOWN AS VESPER UNIT #2-4.

Plugged through: CSG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

PETROLEUM, INC

2-4
#4

LACERTE 'C'

36-9-23W
NW SE NE

Contr. GARVEY DRLG

GRAHAM

County

E 2371RB Comm. 11-7-57

Comp. 1-17-58

IP

59 BOPD/LANS

PERM PMP

Tops	Depth	Datum
ANH	1938	433
HFFB	3610	-1239
TOR	3631	-1260
LANS	3646	-1275
B/KC	3868	-1497
TD	4080	-1709

Casing

8" 236

4" 3970

DST 3647-3745/1 HR, 175' MDY SW, BHP 1000#

DST 3745-95/30", 25' MUD, BHP 460#

DST 3795-3815/1 HR, G/25", 3240' GSY OIL
BHP 1060#

DST 3817-35/1 HR, 7' MUD, BHP 0#

DST 3840-80/1 HR, 35' MDY SPKD OIL, BHP
700#


CO 3914: 24/3823-29: 16/3804-08: 10

G'OPH, NW: NATL: ACID

VESPER POOL

2500: SWB 24 BOPH, NW

4% BASIC SEDIMENT



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

101110