

4-070145

3-29

15-065-03435-0001

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 7-27-51

SW SW NW /4 SEC. 35, 09 S, 23 W
2970 feet from S section line
4950 feet from E section line

Operator license# 5363

Lease: Rice Well # OWWO 1

Operator: Berexco, Inc.

County: Graham 130.00

Address: 100 N. Broadway - #970
Nations Bank Financial Ctr.
Wichita, Kansas 67202

Well total depth 4000 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 191 feet
W/135 sxs.

ABAND. oil well , Gas well , Input well , SWD. , D&A

Plugging contractor: Berexco, Inc. License# 5363

Address: 100 N. Broadway - #970 - Wichita, Kansas 67202

Company to plug at: Hour: 10:00 A.M. Day: 29 Month: March Year: 1999

Plugging proposal received from: Bob Grant

Company: Berexco, Inc. Phone: 316-265-3311

Were: 5 1/2" casing set at 3976' w/200 sxs.
Squeeze at 1045' w/150 sxs. Squeeze at 1654' w/45 sxs. Squeeze at 1150' - 825' with
55sxs and 10% gel.
Perfs at 3734' - 3924'. PBSD 3966'.
Ordered out 300 sxs 60/40 pozmix - 10% gel with 800# hulls.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All , Part , None

Completed: Hour: 4:00 P.M. Day: 29, Month: March, Year: 1999

Actual plugging report: Ran tubing to 3964'. Allied pumped 100 sxs 60/40 pozmix - 10% gel
with 300# hulls. Pulled tubing to 2591' - pumped 100 sxs with 200# hulls. Pulled to 1218'
pumped 75 sxs with 200# hulls. Circulated cement out 8 5/8". PTOH. Squeezed 25 sxs cement.
Max. P.S.I. 600#. S.I.P. slowly bled off to 0#. Shut in. 8 5/8" and pressured up 5 1/2"
casing to 500# and shut in. Hole staying full - pressure slowly bled off.

Remarks: Three previous squeeze jobs never held pressure.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2450 GL

I did / did not observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED

RECEIVED
STATE CORPORATION COMMISSION
4-7-99
APR 7 1999

DATE 4-8-99

INV. NO. 60805

CONSERVATION DIVISION
Wichita, Kansas