

To: 6 030895
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-~~WA~~ 065-01604-00-01

2T
KCC C SE SW, SEC. 4, T 9 S, R24 W4E
660 460 feet from S section line
2300 3400 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6718

Operator: Fell Oil and Gas. Co.
Name & Address: Box 9487
Tulsa, Ok. 74157

Lease Name Keith E. South Well # 3 SWD

County Graham 131.98

Well Total Depth 4061 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 199'

Abandoned Oil Well Gas Well Input Well ^{RT} X KCC SWD Well SWD D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 4 Month: 6 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone)

were: 8 5/8 set @ 199 cuc. 5 1/2 set at 4060' w/ 150 sx PBTD 4030"

Top Perf. 3958' - 63' order sand and com. cmt. Pull pipe

Order 200 sx ATL 65/35 pox 10% gel 2 % dicel, Allied Cmt. Co.

Wellbrock Water Trucks

Plugging Proposal Received by Carl Goodrow *Carl Goodrow*
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part None

Operations Completed: Hour: 3:30PM Day: 4 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT Dump sand on PBTD to 3900' w/ 5 sx com. cmt.

on sand w/bailer 2 shots at 1400' and 1200' recovered 1200' of 5 1/2 casing.

Mix and pump down 8 5/8" w/200 sx ATL blend Max. PSI 400 #

Close in 150 # Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
7-16-87
JUL 16 1987

Remarks: Very little stretch pipe held tight in hole
(if additional description is necessary, use BACK of this form.)

INVOICED I did not observe this plugging.

DATE 7-20-87

Signed *Carl Goodrow*
(TECHNICIAN)

Carl Goodrow

INV. NO. 17523