

To: 6 0-30896
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-01605-0000
NA
NW SW SW, SEC. 4, T 9 S, R 24 W/B
RT 990 WEL feet from S section line
KCC 4950 NSL feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6718
Operator: Fell Oil and Gas Co.
Name & Address Box 9487
Tulsa, Ok. 74157

Lease Name Keith E. Southwell # 4
County Graham 131.79
Well Total Depth 4055 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 192'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing License Number 6050
Address Chase, Kansas

Company to plug at: Hour: PM Day: 4 Month: 6 Year: 19 87

Plugging proposal received from Millard Kelso
(company name) Kelso Casing (phone) _____

were: 8 5/8 set @ 192' w/ 150 sx 5 1/2" set @ 4028' w/ 125 sx PBTB 3994
Perf 3950' - 54' order sand and com cmt. Pull pipe
order 200 sx ATL 65/35 poz 10% gel 2 % dicel 6 sx hulls, Allied Cmt. Co.
Wellbrock Water Truck

Plugging Proposal Received by Carl Goodrow Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:45PM Day: 4 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT Dump sand on PBTB to 3900' w/ 5 sx com cmt. on sand w/bailer
one shot at 1200' recovered 1200' of 5 1/2 casing.
mix and pump down 8 5/8 175 sx cmt. blend w/ 6 sx hulls
max. PSI 500 # close in 150 # plug complete.

APPROVED
STATE CORPORATION COMMISSION
7-16-87
JUL 16 1987
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Very little stretch pipe held tightly in hole
(If additional description is necessary, use BACK of this form.)

INVOICED should not observe this plugging.

DATE 7-20-87
INV. NO. 17519

Signed Carl Goodrow Carl Goodrow
(TECHNICIAN)