

7-21 4-032364

15-065-0160300-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 5-3-57

C NW NE /4 SEC. 04 , 09 , 24 W  
4620 feet from S section line  
1980 feet from E section line

Operator license# 100

Lease: Keith "E" Well # WA1

Operator: Kansas Corporation Commission  
State of Kansas Fee Fund  
Address: 2301 E. 13<sup>th</sup> Street  
Hays, Kansas 67601  
Control #990081-009

County: Graham  
Well total depth 4055 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 193 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Poe Servicing, Inc. License# 3152

Address: Oberlin, Kansas 67749

Company to plug at: Hour: P.M. Day: 21 Month: July Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 11:00 A.M., Day: 21 Month: July, Year: 1999

Actual plugging report: 8 5/8" set at 193' cwc. 5 1/2" set at 4054' w/N/A sxs.  
Prod Perfs 3950' - 3954'. Critical area control shots at 1225' and 2160'. Squeezed 5 1/2"  
with 250 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 800#.  
Close in P.S.I. 100#. Squeezed 8 5/8" annulus with 50 sxs cement blend to Max. P.S.I. 300#.  
Close in P.S.I. 100#. Plug complete.

Remarks: Allied Cement Company  
Condition of casing(in hole): GOOD      BAD      Anhy.plug: YES X NO       
Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING     . Elevation:      GL

I did[ X ] / did not[      ] observe the plugging.

Carl Goodrow  
(agent)

HO

RECEIVED  
STATE CORPORATION COMMISSION  
8-11-99  
AUG 11 1999

Form CP-2/3

CONSERVATION DIVISION  
Wichita, Kansas

①