

4-032367

15-065-01597-00-00

7-19

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 5-27-55

SE SE NE /4 SEC. 04 , 09 , 24 W
2970 feet from S section line
330 feet from E section line

Operator license# 106

Lease: Keith Well # 7

Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #990081-014

County: Graham
Well total depth 4024 ⁷ _{ft} ^{rec} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 201 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Poe Servicing, Inc. License# 3152

Address: Oberlin, Kansas 67749

Company to plug at: Hour: A.M. Day: 19 Month: July Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 9:30 A.M., Day: 19 Month: July, Year: 1999

Actual plugging report: 8 5/8" set at 201' cwc. 5 1/2" set at 4024' w/N/A sxs.
Prod Perfs 3938' - 3943'. Critical area control shots at 1200' and 2160'. Squeezed 5 1/2"
with 250 sxs cement blend with 450# hulls mixed in to Max. P.S.I. 800#.
Close in P.S.I. 200#. Squeezed 8 5/8" annulus with 50 sxs cement blend w/50# hulls mixed in
to Max. P.S.I. 200#. Close in P.S.I. 100#. Plug complete.

Remarks: Allied Cement Company

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

RECEIVED
STATE CORPORATION COMMISSION
8-11-99
AUG 11 1999

Form CP-2/3

CONSERVATION DIVISION
Wichita, Kansas

②