

4-032379

15-065-61595-00-00

7-20

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 2-12-55

NW SW SE /4 SEC. 04 , 09 , 24 W
990 feet from S section line
2310 feet from E section line

Operator license# 100

Lease: Keith Well # 5

Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #990081-020

County: Graham
Well total depth 4500 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 198 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Poe Servicing, Inc. License# 3152

Address: Oberlin, Kansas 67749

Company to plug at: Hour: A.M. Day: 20 Month: July Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 8:30 A.M., Day: 20 Month: July, Year: 1999

Actual plugging report: 8 5/8" set at 190' w/N/A sxs. 5 1/2" set at 4011' w/N/A sxs.
Prod Perfs 3911' - 3920'. Critical area control shots at 1180' and 2110'. Squeezed 5 1/2"
with 300 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 700#. Close in P.S.I.
100#. Squeezed 8 5/8" annulus with 50 sxs cement blend to Max. P.S.I. 100#. Close in P.S.I.
100#. Plug complete.

Remarks: Allied Cement Company

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

100

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
8-11-99
AUG 11 1999

CONSERVATION DIVISION
Wichita, Kansas

8